Exhibit No.

Issues: In-Service Criteria;

New Plant In-Service;

Energy Supply Operating &

Maintenance Expense

Witness: Blake A. Mertens

Type of Exhibit: Direct Testimony Sponsoring Party: Empire District

Docket No.:

Date: October 2009

## Before the Corporation Commission of the State of Kansas

**Direct Testimony** 

Of

Blake A. Mertens

October 2009



# TABLE OF CONTENTS OF BLAKE A. MERTENS ON BEHALF OF THE EMPIRE DISTRICT ELECTRIC COMPANY BEFORE THE KANSAS CORPORATION COMMISSION

1	INTRODUCTION	1
2	EXECUTIVE SUMMARY	2
3	RIVERTON UNIT 12	2
4	ASBURY SCR	3
5	IATAN UNIT 1 AIR QUALITY CONTROL SYSTEM ("AQCS") ADDITIONS	4
6	COAL PLANT INVESTMENTS	5
7	IATAN UNIT 2	7
8	PLUM POINT UNIT 1	7
9	CAPITAL COSTS ASSOCIATED WITH NEW PLANT IN-SERVICE	8
10	O&M ADJUSTMENTS ASSOCIATED WITH NEW GENERATION FACILITIES	11
11	ENERGY SUPPLY OPERATING AND MAINTENANCE ADJUSTMENT	12
12	ENERGY COST ADJUSTMENT ("ECA") INCLUSION OF AQCS CONSUMABLES	13

# DIRECT TESTIMONY OF BLAKE A. MERTENS ON BEHALF OF THE EMPIRE DISTRICT ELECTRIC COMPANY BEFORE THE KANSAS CORPORATION COMMISSION DOCKET NO.

### 1 INTRODUCTION

- 2 Q. PLEASE STATE YOUR NAME AND BUSINESS ADDRESS.
- 3 A. Blake A. Mertens. My business address is 602 South Joplin Avenue, Joplin,
- 4 Missouri.
- 5 Q. BY WHOM ARE YOU EMPLOYED AND IN WHAT CAPACITY?
- 6 A. The Empire District Electric Company ("Empire" or "Company"), I am Associate
- 7 Director of Strategic Projects.
- 8 Q. PLEASE DESCRIBE YOUR EDUCATIONAL BACKGROUND.
- 9 A. I graduated from Kansas State University in 2000 with a Bachelor of Science
- Degree in Chemical Engineering with a minor in Business. I received a Masters
- Degree in Business Administration from Missouri State University in December of
- 12 2007. I am also a professionally licensed engineer in the state of Kansas.
- 13 Q. PLEASE GIVE AN OVERVIEW OF YOUR PROFESSIONAL
- 14 EXPERIENCE.
- 15 A. I was employed by Black & Veatch Corp. immediately following my graduation
- from Kansas State University in May of 2000. From June of 2000 through
- November of 2001, I held roles as a technical analyst and energy consultant for the
- 18 Strategic Planning Group of Black & Veatch's Power Sector Advisory Services in
- 19 the Energy Services Division. Duties included assisting in power plant siting
- 20 studies, economic analysis of potential power plants using production cost
- 21 modeling, independent engineering evaluations of plant assets, and market analysis
- of the California energy crisis of 2000 2001. I went to work for Empire in
- November of 2001 as a Staff Engineer in Energy Supply where my duties included
- 24 tracking of plant capital and operating & maintenance ("O&M") expenses,
- 25 involvement in energy supply regulatory issues, evaluation of new generating

1 resource options, assisting in the construction of new plant, and assisting in the 2 modeling and tracking of fuel and purchased power costs. In 2003, my title was changed to Planning Engineer with similar duties but more responsibilities in the 3 area of generation planning. In the fall of 2004 I took a position as Combustion 4 Turbine Construction Project Manager. In this position I was responsible for the 5 construction and commissioning of a 150 megawatt ("MW") combustion turbine at 6 Empire's Riverton Power Plant known as Riverton Unit 12. Riverton Unit 12 went 7 8 into commercial operation in April of 2007. In the fall of 2006 I took on the position of Manager of Strategic Projects. In this role I was responsible for the 9 10 management of new generation and major projects for Energy Supply facilities. 11 This includes representing Empire's interests at the Iatan, Plum Point and other off-12 system generation facilities. In March of 2009 I was promoted to my current 13 position as Associate Director of Strategic Projects. My duties remain much the same as my previous position but with a broader focus on company-wide projects 14 15 rather than those just related to Energy Supply.

### 16 EXECUTIVE SUMMARY

- 17 Q. WHAT IS THE PURPOSE OF YOUR DIRECT TESTIMONY IN THIS
- 18 CASE BEFORE THE KANSAS CORPORATION COMMISSION
- 19 ("COMMISSION")?
- 20 A. I will quantify and describe the investment Empire has made in new power
- 21 production facilities. These new facilities include the Riverton Unit 12 combustion
- 22 turbine, the Asbury Selective Catalytic Reduction ("SCR") system, the Air Quality
- 23 Control System ("AQCS") at Iatan Unit 1, the Plum Point Unit 1 coal-fired
- 24 generating unit and the Iatan Unit 2 coal-fired generating unit. The ongoing
- operating and maintenance expenses associated with these new generating units will
- also be quantified.

27

### RIVERTON UNIT 12

- 28 Q. PLEASE BRIEFLY EXPLAIN THE RIVERTON UNIT 12 ADDITION.
- 29 A. In July of 2003 it was determined that in order for Empire to economically meet the
- 30 continually growing capacity and energy needs of its customers and service
- territory, additional combustion turbine generating capacity would be needed by the

- summer of 2007. Over the next year Empire evaluated several different sites and
- 2 combustion turbine technologies and manufacturers to determine how to most
- 3 economically meet this need. In the fall of 2004 Empire determined the Riverton
- 4 Power Plant and a Siemens V84.3A2 combustion turbine would be the site and
- 5 combustion turbine of choice, respectively. During 2005 site preparation activities
- 6 took place, leading to construction of the combustion turbine and balance of plant
- facilities in 2006, and commissioning of the unit in 2007. On April 10, 2007
- 8 Empire declared Riverton Unit 12 available for commercial operation.

### 9 Q. DO YOU HAVE PROPOSED IN-SERVICE CRITERIA FOR RIVERTON

- 10 UNIT 12?
- 11 A. Yes, I do. Please refer to Schedule BAM-1 for the in-service criteria utilized in
- 12 Empire's Missouri regulatory proceedings to determine in-service for Riverton Unit
- 13 12.

### 14 Q. HAS RIVERTON UNIT 12 MET EACH OF THE IN-SERVICE

- 15 CRITERIONS?
- 16 A. Yes. Riverton Unit 12 went into commercial operation in April of 2007.
- 17 Documentation supporting the unit's ability to meet the in-service criteria was
- supplied to the Missouri Public Service Commission ("MPSC") Staff during
- 19 Empire's 2008 rate request in Missouri (ER-2008-0093). MPSC Staff agreed the
- 20 criteria had been met in the MPSC Staff's "Cost of Service" report which includes
- 21 supporting testimony from MPSC Staff expert Mike Taylor stating the unit had met
- 22 in-service criteria.

### 23 ASBURY SCR

### 24 O. PLEASE BRIEFLY EXPLAIN THE CIRCUMSTANCES LEADING TO

- 25 THE DECISION TO CONSTRUCT THE ASBURY SCR.
- 26 A. The EPA issued its final Clean Air Interstate Rule ("CAIR") on March 10, 2005.
- 27 The CAIR governs NO<sub>x</sub> and SO<sub>2</sub> emissions from fossil fueled units greater than 25
- 28 megawatts and will affect 28 states, including Missouri, where our Asbury, Energy
- 29 Center, State Line and Iatan Plants are located and Arkansas, where the future Plum
- Point Energy Station will be located. To help meet CAIR NO<sub>x</sub> requirements, we
- 31 constructed a SCR at Asbury.

### 1 Q. DO YOU HAVE PROPOSED IN-SERVICE CRITERIA FOR THE ASBURY

- 2 SCR?
- 3 A. Yes. Please refer to Schedule BAM-2 for the in-service criteria utilized in Empire's
- 4 last Missouri rate case to determine in-service for the Asbury SCR.
- 5 O. HAS THE ASBURY SCR MET EACH OF THESE IN-SERVICE
- 6 CRITERION?
- 7 A. Yes. The Asbury SCR went into service in February of 2008. Documentation
- 8 supporting the unit's ability to meet the in-service criteria was supplied to the
- 9 MPSC Staff during Empire's 2008 rate request in Missouri (ER-2008-0093). In
- 10 MPSC Staff witness Mark Oligschlaeger's True-up Direct Testimony, MPSC Staff
- agreed the criteria had been met.
- 12 IATAN UNIT 1 AIR QUALITY CONTROL SYSTEM ("AQCS") ADDITIONS.
- 13 Q. PLEASE DESCRIBE EMPIRE'S INTERESTS AT THE IATAN PLANT.
- 14 A. Empire has an undivided twelve percent (12%) ownership share of latan Units 1
- and 2. The Greater Missouri Operating Company ("GMOC") has an 18% interest
- in the plant. Kansas City Power & Light ("KCPL") is the majority owner and
- 17 Operator of the plant. As Operator, KCPL is directly responsible for the day to day
- operations of the plant as well as construction management. Empire is responsible
- for its 12% share of operating, maintenance, fuel, construction, and other
- 20 miscellaneous costs at the Iatan plant.
- 21 Q. PLEASE BRIEFLY EXPLAIN THE AQCS ADDITIONS AT IATAN UNIT 1.
- 22 A. The AQCS additions at Iatan Unit 1 include a Selective Catalytic Reduction
- 23 ("SCR") system for the removal of nitrogen oxides ("NOx"), a wet scrubber for the
- removal of sulfur dioxides ("SOx"), a fabric filter bag house for the removal of
- 25 particulate matter, and a powder activated carbon system for the removal of
- 26 mercury. These additions were made in order to comply with EPA regulations and
- 27 to ensure total emissions from the latan site after the addition of latan Unit 2 would
- be less than current (pre-2008) emission levels from a single unit (i.e. the combined
- 29 emission levels from Iatan Unit 1 and Unit 2 will be less than the emission levels
- from Unit 1 prior to these projects commencing). The Iatan Unit 1 AQCS additions

- were contemplated and approved as part of Empire's Regulatory Plan in Missouri
- 2 (EO-2005-0263).

### 3 Q. DO YOU HAVE PROPOSED IN-SERVICE CRITERIA FOR THE IATAN

- 4 UNIT 1 AQCS ADDITIONS?
- 5 A. Yes. The in-service criteria used to determine in-service for the Iatan Unit 1
- 6 AQCS additions in KCPL's recent rate case, ER-2009-0089, are attached to my
- 7 testimony as Schedule BAM-3. Empire submits that these same criteria should be
- 8 used to determine in-service for Empire's share of the Iatan Unit 1 AQCS additions.
- 9 Q. ARE THE IATAN UNIT 1 AQCS ADDITIONS IN-SERVICE?
- 10 A. Yes. These additions went into service as of April 19, 2009. The MPSC Staff
- agreed the in-service criteria had been met in KCPL's recent case (refer to Mr.
- Michael Taylor's oral testimony in Missouri case ER-2009-0089, Item #286) with
- no objections or evidence otherwise presented by other parties.
- 14 COAL PLANT INVESTMENTS
- 15 Q. PLEASE BRIEFLY EXPLAIN THE DECISION PROCESS LEADING UP
- 16 TO EMPIRE'S PARTICIPATION IN IATAN UNIT 2 AND PLUM POINT
- 17 **UNIT 1.**
- 18 A. As part of Empire's ongoing Integrated Resource Planning ("IRP") process, in the
- 19 first half of this decade Empire identified the need for additional base load
- 20 generation in the 2010 timeframe. This new base load generation requirement was
- 21 due in large part to the May 31, 2010 expiration of a purchased power agreement
- Empire has in place with Westar for 162 MW of capacity and energy from Westar's
- 23 Jeffrey Energy Center ("JEC"), a facility with three base load coal units. The IRP
- 24 process determined the most economical option, and the option with the least
- 25 impact to Empire's revenue requirement, was to replace the JEC contract through a
- 26 mix of ownership and/or purchased power agreements in large scale coal-fired
- 27 units.
- 28 Q. DID EMPIRE INVESTIGATE EXTENDING THE PURCHASE POWER
- 29 AGREEMNT WITH WESTAR?

- 1 A. Yes, Empire contacted Westar and tried to negotiate an extension of the JEC
- 2 purchase power agreement. Ultimately, Westar declined to extend the contract and
- 3 Empire had to pursue other options

### 4 Q. WHAT CIRCUMSTANCES LEAD TO EMPIRE'S PARTICIPATION IN

### 5 THE IATAN UNIT 2 PROJECT?

6

- A. As part of the IRP process, Empire evaluated several coal-fired generation options,
- 7 including participating in the Sand Sage project in southwest Kansas, jointly
- 8 building a new coal-fired unit within Empire's service territory, or building
- 9 additional coal-fired generation at Empire's Asbury plant. Ultimately these options
- either did not progress to the construction phase on a timely basis or did not prove
- as economical as the options that Empire chose to pursue at the time Empire made
- its participation decision. The possibility of an additional unit at the Iatan plant had
- been contemplated essentially since Unit 1 went into operation in the early 1980's.
- 14 The option of a second unit at an existing plant has always had appeal to Empire.
- As circumstances would have it, KCPL, Aquila (now Greater Missouri Operating
- 16 Company), and Empire, the owners of Iatan Unit 1, all had base load generation
- 17 needs arising in the 2010 timeframe. Through a collaborative experimental
- regulatory process that took place in the states of Kansas and Missouri, the decision
- was made to move forward with the construction of Iatan Unit 2. While it was at
- 20 times contemplated that Empire may own more than approximately 100 MW of
- 21 Iatan Unit 2, ultimately the design of the unit called for an 850 MW unit and an
- 22 ownership agreement was negotiated to allow Empire to own 12% of Iatan Unit 2,
- the same percentage as Empire's ownership share in Iatan 1.

### 24 Q. WHY DID EMPIRE PARTICIPATE IN THE PLUM POINT UNIT 1

### 25 **PROJECT?**

- 26 A. As previously stated, Empire needed to replace the 162 MW purchased power
- agreement tied to JEC. Since its participation in Iatan Unit 2 was limited to
- approximately 100 MW, Empire needed to find another base load generation
- 29 source, preferably coal fired. LSPower, a developer of power plants in the
- 30 Midwest, had approached Empire on several occasions in the first half of this
- decade about the possibility of participating in Plum Point Unit 1. While this

- 1 project always appeared to have potential, LSPower struggled to find enough 2 partners to participate in the project to allow it to move forward. Finally in late 2005 / early 2006, LSPower garnered enough participants to allow the project to 3 move forward. This was approximately at the same time Empire was negotiating its 4 participation agreement with Iatan Unit 2 and realizing its participation was going 5 to be limited to approximately 100 MW. After analyzing the Plum Point Unit 1 6 7 project and Empire's financial situation, it was decided that a 50 MW ownership 8 position in the unit and an additional 50 MW purchased power agreement from the unit would be most prudent. These decisions were made as part of Empire's 9 10 ongoing IRP process and conveyed to the parties involved in Empire's Missouri IRP as well as pertinent regulatory parties in Kansas. 11
- 12 IATAN UNIT 2
- 13 Q. PLEASE BRIEFLY EXPLAIN THE IATAN UNIT 2 ADDITION.
- 14 A. Iatan Unit 2 is an approximately 850 MW, supercritical, pulverized coal-fired
- 15 generating unit located at the Iatan site near Weston, Missouri. This unit is jointly
- owned by KCPL, GMOC, Empire, Missouri Joint Municipal Electric Utility
- 17 Commission ("MJMEUC"), and Kansas Electric Power Cooperative ("KEPCO").
- 18 Empire's share of Iatan Unit 2 is 12 % or approximately 102 MW. This unit has
- been under construction since early 2006 and is scheduled to be available for
- service late in the summer of 2010. Empire's ownership in Iatan Unit 2 was also
- 21 contemplated and approved as part of Empire's Regulatory Plan in Missouri (EO-
- 22 2005-0263).
- 23 Q. DO YOU HAVE PROPOSED IN-SERVICE CRITERIA FOR THE IATAN
- 24 UNIT 2 ADDITION?
- 25 A. Yes. Attached as Schedule BAM-4 is the in-service criteria KCPL, the MPSC
- Staff, and Empire have jointly drafted for Iatan Unit 2.
- 27 Q. HAS IATAN UNIT 2 MET THE IN-SERVICE CRITERIA?
- 28 A. No. As previously stated the unit is not scheduled to be in-service until late in the
- summer of 2010. I present the in-service criteria here for reference only so that it is
- 30 clear what criteria will be used at a later time to determine in-service.

### PLUM POINT UNIT 1

31

### 1 Q. PLEASE BRIEFLY EXPLAIN THE PLUM POINT UNIT 1 ADDITION.

- Plum Point Unit 1 is an approximately 665 MW, subcritical, pulverized coal-fired 2 A. generating unit located near Osceola, Arkansas (the northeast corner of Arkansas 3 along the Mississippi River). This unit is jointly owned by Plum Point Energy 4 Associates, LLC ("PPEA"), (which is a partnership between Dynegy, John Hancock, and Energy Investment Fund), East Texas Electric Cooperative 6 ("ETEC"), Inc., Empire, MJMEUC, and Municipal Energy Association of 7 8 Mississippi ("MEAM"). Empire's ownership share of Plum Point Unit 1 is 7.52% or approximately 50 MW. Empire also has a purchase power agreement with PPEA 9 10 for an additional 50 MW of capacity and associated energy from the unit. This unit 11 has been under construction since early 2006 and is scheduled to be available for 12 service in the summer of 2010. Empire's stake in Plum Point Unit 1 was not 13 specifically contemplated and approved as part of Empire's Missouri Regulatory 14 Plan, but was contemplated and discussed as part of Empire's ongoing Missouri IRP, which is filed at the MPSC and discussed on an ongoing basis with MPSC 15 Staff, the Office of Public Counsel ("OPC"), and other interested parties involved in 16 17 Empire's regulatory proceedings in Missouri.
- 18 Q. DO YOU HAVE PROPOSED IN-SERVICE CRITERIA FOR THE PLUM 19 POINT UNIT 1 ADDITION?
- A. Yes. Attached as Schedule BAM-5 is the in-service criteria the MPSC Staff and Empire have agreed to for Plum Point Unit 1. These criteria are largely the same as the criteria used for Iatan Unit 2 except for adaptations for specific Plum Point Unit 1 contract guarantee and capacity values.
- 24 Q. HAS PLUM POINT UNIT 1 MET THE IN-SERVICE CRITERIA?
- A. No. As previously stated the unit is not scheduled to be in-service until the summer of 2010. I present the in-service criteria here for reference only so it is clear what criteria will be used at a later time to determine in-service.
- 28 CAPITAL COSTS ASSOCIATED WITH NEW PLANT IN-SERVICE
- Q. HAVE THE CAPITAL COSTS ASSOCIATED WITH THE
  AFOREMENTIONED PROJECTS BEEN INCLUDED IN THE REVENUE
  REQUIREMENT IN THIS RATE CASE?

- 1 A. Yes. The filing includes the capital costs associated with Riverton Unit 12, Asbury
- 2 SCR, Empire's share of Iatan Unit 1 AQCS additions, Empire's share of Iatan Unit
- 3 2, Empire's share of Plum Point Unit 1.
- 4 Q. FOR PURPOSES OF THIS RATE CASE, WHAT LEVEL OF
- 5 EXPENDITURES ARE INCLUDED FOR THESE SPECIFIC CAPITAL
- 6 **ADDITIONS?**
- 7 A. In total, Empire's filing reflects \$499,905,058 in total investment for these capital
- 8 additions which is inclusive of incurred and projected capital expenditures and
- 9 AFUDC. The Kansas jurisdictional share of the overall capital investment in these
- five (5) capital projects is approximately 5.65% or \$28.2 million.
- 11 Q. ARE THERE ANY FACTORS THAT COMPLICATE HOW THE
- 12 AMOUNTS INCLUDED FOR THESE CAPITAL ADDITIONS ARE
- 13 **REPORTED?**
- 14 A. Yes.
- 15 Q. PLEASE EXPLAIN.
- 16 A. Specifically as it relates to the Iatan projects, a portion of the Iatan Unit 1 AQCS
- additions and Iatan Unit 2 project include plant that is designated as Common
- Property. This designation is for equipment that will be utilized by both Unit 1 and
- 19 Unit 2, such as the stack shell, limestone handling, fuel handling, etc. This
- designation had to be made due to the fact that the two units have different
- ownership structures (i.e. KEPCO and MJMEUC are part owners of Unit 2 but not
- of Unit 1). From Empire's overall cost perspective this designation is
- 23 inconsequential since we are a 12-percent owner in both units; however, from a
- 24 total project accounting and plant in-service perspective this is of importance.
- 25 Q. PLEASE CONTINUE.
- 26 A. When the Iatan Unit 1 AQCS additions went into service, FERC accounting
- 27 regulations (specifically 18 CFR Ch.1, Section 107.B) require Common Plant to be
- 28 placed in-service at the same time. This proved problematic as the Iatan Unit 1
- 29 AQCS and Iatan Unit 2 project budgets included Common Property items in both of
- them. In other words, there was not a separate budget for Iatan Common Property.
- 31 As a result an evaluation of Common Property had to be made to determine what

- portion of each of the Iatan project budgets were Common Property and thus had to
- 2 be placed in-service. This evaluation did not change the overall budget for the
- 3 Iatan projects, but does create some confusion when presenting project actual
- 4 expenditures compared to project budgets.
- 5 Q. WHEN YOU REFER TO THE AMOUNTS OF COMMON PROPERTY
- 6 INCLUDED IN THE IATAN 1 AQCS AND IATAN 2 PROJECT BUDGETS,
- 7 COULD YOU PLEASE BE MORE SPECIFIC?
- 8 A. Excluding AFUDC and property taxes, the total shared Iatan Unit 1 AQCS budget
- 9 is approximately \$484 million (Empire's share \$58.1 million) of which
- approximately \$114 million (Empire's share \$13.7 million) is Common Property.
- Likewise, excluding AFUDC and property taxes, Iatan Unit 2's current total shared
- budget is approximately \$1.9 billion (Empire's share \$228 million) of which \$269
- million (\$32.2 million Empire's share) is Common Property.
- 14 Q. WITH THE IATAN COMMON PROPERTY ISSUE IN MIND, PLEASE
- 15 PROVIDE FURTHER DETAIL ON THE APPROXIMATELY \$500
- 16 MILLION BEING INCLUDED AS NEW PLANT IN-SERVICE FOR THESE
- 17 **PROJECTS.**
- 18 A. Yes. Please refer to Schedule BAM-6 which summarizes the current budgets for
- each of the ongoing projects at Iatan and Plum Point Unit 1 excluding AFUDC, the
- amounts incurred through June 30, 2009, the amount of AFUDC accrued through
- June 30, 2009, the amounts reflected as plant in-service as of June 30, 2009 (end of
- 22 test year) for Iatan Unit 1 AQCS and Iatan Common Property, and the projected
- 23 amounts of expenditures and AFUDC accruals through project completion. These
- ongoing projects total approximately \$425 million of the \$500 million. The other
- approximately \$75 million is comprised of \$42,318,070 for Riverton Unit 12 which
- went into service in April 2007 and \$32,335,403 for the Asbury SCR which went
- into service in February 2008.
- 28 O. DO YOU EXPECT THE FULL \$500 MILLION TO BE EXPENDED AS OF
- 29 THE DATE RATES ARE EFFECTIVE FOR THIS CASE?
- 30 A. No. Since the Iatan Unit 2 and Plum Point Unit 1 projects are not scheduled to go
- into service until sometime in the summer of 2010 and rates are to be effective

- shortly thereafter, there will undoubtedly be costs that have not been invoiced
- and/or approved by the date rates become effective in this case. Please refer to
- 3 Empire witness Kelly Walters' direct testimony for a description of how Empire
- 4 proposes the cost of these new plant additions will be recovered in its rates over
- 5 time.

### 6 <u>O&M ADJUSTMENTS ASSOCIATED WITH NEW GENERATION FACILITIES</u>

- 7 Q. BEYOND CAPITAL EXPENSES, ARE THERE ANY OTHER COSTS
- 8 ASSOCIATED WITH THESE PROJECTS THAT SHOULD BE
- 9 ACCOUNTED FOR AND REFLECTED IN RATES?
- 10 A. Yes. Specifically the ongoing operating, maintenance, fuel, transmission, and other
- miscellaneous costs associated with ongoing operations of these facilities need to be
- accounted for and reflected in Empire's rates for electric service. No adjustments
- are proposed for Riverton Unit 12 since it has been in operation since April 2007
- and ongoing operating and maintenance costs for this unit are included in the test
- 15 year.
- 16 Q. PLEASE SUMMARIZE THE O&M ADJUSTMENTS YOU ARE
- 17 SUPPORTING IN THIS RATE CASE FOR THESE FACILITIES.
- 18 A. The proposed adjustments to operating and maintenance ("O&M") expense for
- 19 Iatan 2 total \$3,858,276, which is inclusive of ammonia, limestone, and powder
- activated carbon for the Unit 2 AQCS. This adjustment is based on the projected
- O&M budget KCP&L has prepared for the plant for the year 2011, the units first
- full year of operation. The proposed adjustments to O&M expenses for Plum Point
- 23 Unit 1 plant \$2,783,975. This adjustment is based on an O&M budget prepared by
- Dynegy Services Plum Point ("DSPP"), a subsidiary of Dynegy in charge of Plum
- 25 Point Unit 1 project management, and North America Energy Services, the third
- party O&M provider for the plant. Additionally, an adjustment of \$350,007 has
- been made to the Iatan Unit 1 O&M expenses to account for a full year of operation
- of the AQCS. Since the Unit 1 AQCS did not go into service until late April of
- 29 2009, very few AQCS operating costs are included in the test year, ending June 30,
- 30 2009. This \$350,007 in annual O&M is comprised of the cost of limestone,
- ammonia, and powder activated carbon. Finally, an adjustment of \$216,136 has

- been made for the operation of Iatan Common Property. This adjustment is based
- on the projected O&M budget KCP&L has prepared for the plant for the year 2011.
- 3 Please refer to schedules BAM-7 thru BAM-10 for further detail of these
- 4 adjustments.

### 5 Q. DO YOU PROPOSE A SPECIFIC TRANSMISSION ADJUSTMENT FOR

### 6 ANY OF THE NEW FACILITIES?

- 7 A. Yes. Since Plum Point Unit 1 is located in the Entergy transmission region, Empire
- 8 had to secure firm point-to-point transmission to export the power out of Entergy
- 9 into the Southwest Power Pool ("SPP"), the regional transmission system Empire
- operates within. Entergy's tariff rate effective June 1, 2009 for firm, long-term
- point-to-point transmission is \$1,350 per MW-month. Empire has reserved 100
- MW of firm point-to-point transmission service on Entergy's system, 50 MW for
- the ownership share and 50 MW for the purchase power agreement. This equates to
- 14 \$1,620,000 in annual transmission charges.

### 15 ENERGY SUPPLY OPERATING AND MAINTENANCE ADJUSTMENT

- 16 Q. WHAT AREAS OF ENERGY SUPPLY WILL YOUR TESTIMONY
- 17 ADDRESS AS IT RELATES TO OPERATING AND MAINTENANCE
- 18 ("O&M") EXPENSES?
- 19 A. Energy Supply O&M expenses include operating and maintenance expenses
- 20 incurred at Empire's Asbury, Energy Center, Ozark Beach, Riverton, and State Line
- 21 plants. In addition, Empire's 12-percent share of O&M expenses incurred at the
- 22 KCPL operated latan plant are included in O&M expenses.
- 23 Q. WHAT WAS THE TEST YEAR (TWELVE-MONTHS-ENDING ("TME")
- JUNE 30, 2009) LEVEL OF O&M EXPENSES FOR THESE ENERGY
- 25 SUPPLY FACILITIES, EXCLUDING LABOR?
- A. O&M expenses for TME June 2009 totaled \$10,165,331, which includes 60 percent
- of State Line Combined Cycle's ("SLCC's") O&M expenses. This unit is jointly
- owned Westar owns 40% and Empire owns 60%. Thus, Empire is responsible for
- approximately 60 percent of the O&M costs at SLCC.

- 1 Q. FOR PURPOSES OF THIS CASE, WERE ANY ADJUSTMENTS MADE TO
- 2 THE LEVEL OF EXPENSE TO BETTER REPRESENT NORMAL
- 3 ONGOING O&M EXPENSES IN ENERGY SUPPLY?
- 4 A. Yes. One adjustment was made to the level of O&M expenses for the Asbury SCR
- 5 which was placed into service February of 2008. The proposed adjustment is
- 6 \$354,000. This adjustment is made to realize a full year of operating and
- 7 maintenance expenses for the SCR.
- 8 Q. IF THE SCR WENT INTO SERVICE IN FEBRUARY OF 2008, WOULD A
- 9 FULL YEAR'S WORTH OF EXPENSES BE IN THE TEST YEAR?
- 10 A. Normally, yes; however, since the EPA's new Clean Air Interstate Rule regulations
- for NOx emissions did not go into effect until January of 2009, the SCR did not
- operate at "normal" levels until January of 2009. For this reason little to no
- ammonia was consumed by the SCR in the latter half of 2008. The \$354,000
- adjustment simply doubles the amount of SCR expenses that were actually incurred
- in the first half of 2009 when the SCR was operating normally.
- 16 Q. IS \$708,000 EQUAL TO THE NORMAL ANNUAL OPERATING
- 17 EXPENSES ASSOCIATED WITH THE ASBURY SCR?
- 18 A. Based on existing ammonia prices, this is the best estimate available; however,
- since ammonia prices are highly correlated to natural gas prices, there is a high
- 20 level of uncertainty related to "normal" annual SCR costs. Since natural gas prices
- are currently low, it is more likely that annual SCR costs will be higher rather than
- lower.
- 23 ENERGY COST ADJUSTMENT ("ECA") INCLUSION OF AQCS
- 24 **CONSUMABLES**
- 25 Q. WHAT IS THE PURPOSE OF THIS SECTION OF YOUR TESTIMONY?
- 26 A. I would like to present the argument on why Empire believes the costs associated
- with consumables used in AQCS processes should be included in fuel accounts and
- 28 passed through as part of the ECA. Specifically I am referring to the costs of
- ammonia used by an SCR, the costs of limestone used by scrubbers, and the cost of
- 30 powder activated carbon used in mercury removal processes. Collectively I will
- refer to these as "AQCS consumables".

### 1 Q. AT WHAT GENERATION FACILITIES ARE THESE AQCS

- 2 CONSUMABLES TO BE UTILIZED?
- 3 A. Empire utilizes ammonia in its SCR's at the Asbury and SLCC generating units.
- 4 Empire will pay for its share of AQCS consumables at the Iatan Unit 1, Iatan Unit
- 5 2, and Plum Point Unit 1 generating units.

### 6 Q. WHAT LEVEL OF EXPENSES IS EMPIRE INCLUDING IN THIS RATE

- 7 PROCEEDING FOR AOCS CONSUMABLES?
- 8 A. \$2,165,183. Please refer to Schedule BAM-11 for a breakdown of consumable
- 9 costs by generating unit.

### 10 Q. WHY SHOULD THESE AQCS CONSUMABLE EXPENSES BE

- 11 REFLECTED IN THE ECA?
- 12 A. There are at least three reasons why these costs should be included in the ECA:
- 1) These costs are highly correlated to the amount of fuel consumed and/or electric
- 14 generation produced at these generating units.
- 15 2) The prices of these AQCS consumables are highly variable.
- 16 3) The cost of emission allowances run through the ECA in 509 accounts.

### 17 Q. PLEASE EXPOUND ON EACH OF THE THREE REASONS JUST

- 18 STATED?
- 19 A. The first reason is rather self evident. As more energy is produced from a
- 20 generating unit additional fuel is needed to produce this energy. Likewise, as
- 21 additional fuel is consumed additional AQCS consumables are needed to control
- 22 emissions from the facility. For many of the same reasons that fuel costs run
- 23 through the ECA it makes sense for AQCS consumables that are directly tied to the
- level of fuel used at the generating unit to also run through the ECA. Simply put
- 25 the customer will benefit when AQCS consumables, or variable environmental
- costs, are below base rate levels and the Company will be made whole when AQCS
- consumables, or variable environmental costs, are above base rate levels. For
- 28 example, if demand is above "normal" levels and additional generation is needed to
- serve customers, it is highly likely additional AQCS consumables will be consumed
- 30 to provide this generation. While the ECA allows Empire to recover its prudently
- incurred direct fuel costs, the additional cost of AQCS consumables will not be

reflected in rates. To provide a similar example from the opposite perspective, if
one of Empire's base load units experiences an extended outage, low cost
generation that came from this unit will likely have to be replaced with higher cost
gas generation or purchased power, both of which are likely to cause fewer AQCS
consumables to be consumed. In this case customers will very likely pay for higher
cost energy through the ECA, but would not directly benefit from lower AQCS
operating expenses.

### 8 Q. PLEASE CONTINUE.

A. The second reason for ECA inclusion is related to the volatility of AQCS consumable prices. Just as natural gas and coal are susceptible to price changes due to uncontrollable market factors so are the prices of AQCS consumables. In fact, the ammonia contract in place for Empire's Asbury facility is tied to natural gas price indexes since the cost of natural gas is highly correlated to the production cost of anhydrous ammonia. Since recent history has shown that natural gas prices are highly volatile, so to is the price of anhydrous ammonia.

### 16 Q. PLEASE CONTINUE WITH YOUR FINAL REASON.

17 A. Finally, as it relates to the third reason (costs of emission allowances that are 18 accounted for in FERC account 509 run through the ECA), one must understand the 19 number of emission allowances a company must procure to comply with emission 20 regulations is related to the cost of AQCS consumables. For example, a company can comply with emission regulations by directly investing in emission control 21 22 equipment and/or procuring emission allowances or some combination of the two 23 There is an asymmetrical incentive in place if the ECA captures the 24 proceeds from the sale of an emission allowance, but it does not capture the cost to 25 produce the emission allowance. That appears to be the case in the ECA currently authorized for Empire in Kansas. By placing AQCS consumables in the same 26 27 position as FERC 509 emission allowance costs, the proper symmetry of cost, revenue and recovery is in place. 28

### 29 O. DOES THIS CONCLUDE YOUR DIRECT TESTIMONY?

30 A. Yes, it does.

### Combustion Turbine Unit In-Service Test Criteria (Nameplate Capacity of ≥ 95 MW)

- 1. All major construction work is complete.
- 2. All preoperational tests have been successfully completed.
- 3. Unit successfully meets all contract operational guarantees.
- 4. Unit successfully demonstrates its ability to initiate the proper start sequence resulting in the unit operating from zero (0) rpm (or turning gear) to full load when prompted at a location (or locations) from which it is normally operated.
- 5. If unit has fast start capability, the unit demonstrates its ability to meet the fast start capability.
- 6. Unit successfully demonstrates its ability to initiate the proper shutdown sequence from full load resulting in zero (0) rpm (or turning gear) when prompted at a location (or locations) from which it is normally operated.
- 7. Unit successfully demonstrates its ability to operate at minimum load for one (1) hour.
- 8. Unit successfully demonstrates its ability to operate at or above 95% of nominal capacity for 4 continuous hours.
- 9. Unit successfully demonstrates its ability to produce an amount of energy (MWhr) within a 72 hour period that results in a capacity factor of at least 50% during the period when calculated by the formula: capacity factor = (MWhrs generated in 72 hours) / (nominal capacity x 72 hours).
- 10. Sufficient transmission interconnection facilities shall exist for the total plant design net electrical capacity at the time the unit is declared fully operational and used for service
- 11. Sufficient transmission facilities shall exist for the total plant design net electrical capacity from the generating station into the utility service territory at the time the unit is declared fully operational and used for service.

1

### In-Service Criteria for NO<sub>X</sub> Control Equipment

- 1. All major construction work is complete.
- 2. All preoperational tests have been successfully completed.
- 3. Equipment successfully meets all operational contract guarantees. The operational contract guarantees that have been satisfied by the time of Staff's direct, rebuttal, or surrebuttal testimony filing in the current rate case will be evaluated by the Staff. Note: This applies to operational contract guarantees that are not addressed in criteria 4, 5, and 6 (as listed below).
- 4. The equipment shall be operational and demonstrate its ability to operate at a NO<sub>X</sub> reduction efficiency equal to or greater than 83.7% over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load.
- 5. The equipment shall also demonstrate its ability to operate at a  $NO_X$  reduction efficiency equal to or greater than 79.2% over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load.
- 6. Continuous emission monitoring systems (CEMS) are operational and demonstrate the capability of monitoring the NO<sub>X</sub> emissions to satisfy the parameters in items (4) and (5) above.

1

# In-Service Criteria for Iatan 1--Particulate and Opacity Control Equipment

- 1. All major construction work is complete.
- 2. All preoperational tests have been successfully completed.
- 3. Equipment successfully meets operational contract guarantees. (Note: Some operational contract guarantee verification periods may extend beyond the duration of the schedule for a rate case. These guarantees will be evaluated for applicability.)
- 4. The equipment shall be operational and demonstrate its ability to operate at a stack opacity (six minute average) less than or equal to 11% over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load (670 MWnet).
- 5. The equipment shall also demonstrate its ability to operate at a stack opacity (six minute average) less than or equal to 11.5% over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load (670 MWnet).
- 6. Continuous emission monitoring systems (CEMS) are operational and demonstrate the capability of monitoring the opacity emissions to satisfy the parameters in items (4) and (5) above.

### In-Service Criteria for Iatan 1--NO<sub>X</sub> Control Equipment

- 1. All major construction work is complete.
- 2. All preoperational tests have been successfully completed.
- Equipment successfully meets operational contract guarantees. (Note: Some operational
  contract guarantee verification periods may extend beyond the duration of the schedule
  for a rate case. These guarantees will be evaluated for applicability.)
- 4. The equipment shall be operational and demonstrate its ability to operate at a NO<sub>X</sub> emission level of 0.090 lb/mmBtu over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load (670 MWnet).
- 5. The equipment shall also demonstrate its ability to operate at a NO<sub>X</sub> emission level of 0.100 lb/mmBtu over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load (670 MWnet).
- 6. Continuous emission monitoring systems (CEMS) are operational and demonstrate the capability of monitoring the NO<sub>X</sub> emissions to satisfy the parameters in items (4) and (5) above.

### In-Service Criteria for Iatan 1-SO<sub>2</sub> Control Equipment

- 1. All major construction work is complete.
- 2. All preoperational tests have been successfully completed.
- Equipment successfully meets operational contract guarantees. (Note: Some operational
  contract guarantee verification periods may extend beyond the duration of the schedule
  for a rate case. These guarantees will be evaluated for applicability.)
- 4. The equipment shall be operational and demonstrate its ability to operate at a SO<sub>2</sub> reduction efficiency equal to or greater than 91% over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load (670 MWnet).
- 5. The equipment shall also demonstrate its ability to operate at a SO<sub>2</sub> reduction efficiency equal to or greater than 86% over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load (670 MWnet).
- 6. Continuous emission monitoring systems (CEMS) are operational and demonstrate the capability of monitoring the SO<sub>2</sub> emissions to satisfy the parameters in items (4) and (5) above.

3

### **Iatan Unit 2 In-Service Test Criteria**

1. Unit must demonstrate that it can operate at its design minimum load (340 MWnet) or above.

Hours at or above design minimum load /  $400 \text{ hours} \ge 0.80$ 

2. Unit must be able to operate at or above its design capacity factor for a reasonable period of time. If the design capacity factor is not specified it will be assumed to be 0.60 unless the utility can offer evidence justifying a lower value.

Design capacity factor <= energy generated for a continuous period of 168 hours/ (design full load [850 MWnet] x 168 hours)

- 3. Unit must operate at an average capacity equal to 98% of its design maximum continuous rating [850 MWnet] for four (4) hours.
- 4. Unit must be operated so as to show a clear and obvious trend toward the predominate use of coal as its primary fuel. Test period will be thirty (30) days. The following items will be used as an indication of the trend for coal operation:
  - a) Boiler control tuning completed such that the unit can operate safely with all control systems in auto.
  - b) Ash build up in the furnace and backpass areas shall be monitored and be within expected levels.
  - c) All boiler/turbine interlocks shall be proven to work as designed.
  - d) Sootblowing timing and sequences shall be set properly to clean the tube areas.
  - e) All critical alarms brought into the control room shall be operational and functioning properly.
  - f) At the end of the test period, oil burn levels, if applicable, will be at or near design levels while burning coal.
  - g) Oil ignitors are functioning in accordance with specifications.

1

NP

- h) Coal handling systems, from rail car unloading to pulverizers, are capable of supplying primary fuel for sustained operation during the testing period.
- 5. Unit must have successfully completed all major equipment startup test procedures. For purposes of this paragraph, major equipment includes: steam generator, turbine-generator, cooling tower/circulating water system, boiler feed pump(s), coal receiving/handling equipment, pulverizers, ash-handling equipment, condensate and feedwater systems, combustion air systems, flue gas systems, on-site electrical distribution system, instrumentation and controls systems (including distributed control system), and chemical storage/transfer systems.
- 6. All major equipment operates satisfactorily to support compliance with in-service criteria 1 through 4 (as listed above). For purposes of this paragraph, major equipment includes: steam generator, turbine-generator, cooling tower/circulating water system, boiler feed pump(s), coal receiving/handling equipment, pulverizers, ash-handling equipment, condensate and feedwater systems, combustion air systems, flue gas systems, on-site electrical distribution system, instrumentation and controls systems (including distributed control system), and chemical storage/transfer systems.
- 7. Sufficient transmission interconnection facilities shall exist for the total plant design net electrical capacity at the time the newest unit is declared fully operational and used for service.
- 8. Sufficient transmission facilities shall exist for EDE's share of the total plant design net electrical capacity from the generating station into the EDE service territory at the time the newest unit is declared fully operational and used for service.
- 9. Equipment installed to comply with emission requirements shall be operational and demonstrate the ability to remove 93% or more of the NO<sub>x</sub>, SO<sub>2</sub>, particulate, and mercury emissions they were installed to remove over a continuous four (4) hour period while operating at or above 95% of its design load. This equipment shall also be required to demonstrate that it is able to remove 88% or more of these same emissions it was

2 **NP** 

installed to remove over a continuous 120 hour period while operating at or above 80% of its design load.

10. Emissions Control Equipment. The utility and the Commission Staff agree that the in-service testing requirements of this Paragraph are equivalent to the performance criteria stated in Paragraph 9 above and contained in the Stipulation. Each equipment system as set forth in Subparagraphs (a) – (d) below shall be evaluated for successful completion of in-service testing on an individual basis. The failure of the utility to achieve the emissions or removal limits specified in the in-service testing for a given system will not impact the utility's ability to include all systems demonstrated to meet the applicable emissions or removal limits in the utility's rate recovery regulatory proceeding for Iatan Unit 2.

### a) NO<sub>X</sub> Control Equipment

- i. All major construction work is complete.
- ii. All preoperational tests have been successfully completed.
- iii. Equipment successfully meets the operational contract guarantees necessary to achieve the emission levels described in subparagraphs 10(a)(iv) and 10(a)(v) below.
- iv. The equipment shall be operational and demonstrate its ability to operate at a NO<sub>X</sub> emission level of less than or equal to 0.054 lb/mmBtu over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load (850 MWnet).
- v. The equipment shall also demonstrate its ability to operate at a  $NO_X$  emission level of less than or equal to 0.057 lb/mmBtu over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load (850 MWnet).

### b) SO<sub>2</sub> Control Equipment

3 **NI** 

Paragraph 10 identifies the criteria and emissions/removal testing that will demonstrate the utility's achievement of the criteria contained in Paragraph 9. The language of Paragraph 9 is also contained in the Stipulation. The utility and Staff calculated the numerical values and/or percentages contained in Paragraph 10 from the Iatan Unit 2 design limits for each of the major components of the AQCS equipment and the emissions percent or rate of removal requirements for the testing described in Paragraph 9 and the Stipulation. A chart summarizing the testing requirements is contained in the attached Appendix A.

- i. All major construction work is complete.
- ii. All preoperational tests have been successfully completed.
- iii. Equipment successfully meets the operational contract guarantees necessary to achieve the emission levels described in subparagraphs 10(b)(iv) and 10(b)(v) below.
- iv. The equipment shall be operational and demonstrate its ability to operate at a SO<sub>2</sub> reduction efficiency equal to or greater than 91% over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load (850 MWnet).
- v. The equipment shall also demonstrate its ability to operate at a SO<sub>2</sub> reduction efficiency equal to or greater than 86% over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load (850 MWnet).

### c) Particulate and Opacity Control Equipment

- i. All major construction work is complete.
- ii. All preoperational tests have been successfully completed.
- iii. Equipment successfully meets the operational contract guarantees necessary to achieve the emission levels described in subparagraphs 10(c)(iv) and 10(c)(v) below.
- iv. The equipment shall be operational and demonstrate its ability to operate at a stack opacity (six minute average) less than or equal to 11% over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load (850 MWnet).
- v. The equipment shall also demonstrate its ability to operate at a stack opacity (six minute average) less than or equal to 11.5% over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load (850 MWnet).

### d) Mercury Removal Equipment

- i. All major construction work is complete.
- ii. All preoperational tests have been successfully completed.

4

NP

- iii. Equipment successfully meets the operational contract guarantees necessary to achieve the emission levels described in subparagraphs 10(d)(iv) and 10(d)(v) below.
- iv. The equipment shall be operational and demonstrate its ability to operate at a mercury emission level of less than or equal to 1.61 lb/trillion Btu over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load (850 MWnet).
- v. The equipment shall also demonstrate its ability to operate at a mercury removal level of less than or equal to 1.70 lb/trillion Btu over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load (850 MWnet).

### e) <u>Continuous Emissions Monitoring System</u>

i. Continuous emission monitoring systems (CEMS) are operational and demonstrate the capability of monitoring the emissions to satisfy the parameters in Paragraph 10.

NP

5

# APPENDIX A \*\*Highly Confidential in its Entirety\*\*

6 **NP** 

### Plum Point Unit 1 In-Service Test Criteria

1. Unit must demonstrate that it can operate at its design minimum load (266 MWnet) or above.

Hours at or above design minimum load / 400 hours >= 0.80

2. Unit must be able to operate at or above its design capacity factor for a reasonable period of time. If the design capacity factor is not specified it will be assumed to be 0.60 unless the utility can offer evidence justifying a lower value.

Design capacity factor <= energy generated for a continuous period of 168 hours/ (design full load [665 MWnet] x 168 hours)

- 3. Unit must operate at an average capacity equal to 98% of its design maximum continuous rating [665 MWnet] for four (4) hours.
- 4. Unit must be operated so as to show a clear and obvious trend toward the predominate use of coal as its primary fuel. Test period will be thirty (30) days. The following items will be used as an indication of the trend for coal operation:
  - a) Boiler control tuning completed such that the unit can operate safely with all control systems in auto.
  - b) Ash build up in the furnace and backpass areas shall be monitored and be within expected levels.
  - c) All boiler/turbine interlocks shall be proven to work as designed.
  - d) Sootblowing timing and sequences shall be set properly to clean the tube areas.
  - e) All critical alarms brought into the control room shall be operational and functioning properly.
  - f) At the end of the test period, oil burn levels, if applicable, will be at or near design levels while burning coal.
  - g) Oil ignitors are functioning in accordance with specifications.

- h) Coal handling systems, from rail car unloading to pulverizers, are capable of supplying primary fuel for sustained operation during the testing period.
- 5. Unit must have successfully completed all major equipment startup test procedures. For purposes of this paragraph, major equipment includes: steam generator, turbine-generator, cooling tower/circulating water system, boiler feed pump(s), coal receiving/handling equipment, pulverizers, ash-handling equipment, condensate and feedwater systems, combustion air systems, flue gas systems, on-site electrical distribution system, instrumentation and controls systems (including distributed control system), and chemical storage/transfer systems.
- 6. All major equipment operates satisfactorily to support compliance with in-service criteria 1 through 4 (as listed above). For purposes of this paragraph, major equipment includes: steam generator, turbine-generator, cooling tower/circulating water system, boiler feed pump(s), coal receiving/handling equipment, pulverizers, ash-handling equipment, condensate and feedwater systems, combustion air systems, flue gas systems, on-site electrical distribution system, instrumentation and controls systems (including distributed control system), and chemical storage/transfer systems.
- 7. Sufficient transmission interconnection facilities shall exist for the total plant design net electrical capacity at the time the unit is declared fully operational and used for service.
- 8. Sufficient transmission facilities shall exist for EDE's share of the total plant design net electrical capacity from the generating station into the EDE service territory at the time the unit is declared fully operational and used for service.
- 9. Equipment installed to comply with emission requirements shall be operational and demonstrate the ability to remove 93% or more of the NO<sub>X</sub>, SO<sub>2</sub>, particulate, and mercury emissions they were installed to remove over a continuous four (4) hour period while operating at or above 95% of its design load. This equipment shall also be required to demonstrate that it is able to remove 88% or more of these same emissions it was

installed to remove over a continuous 120 hour period while operating at or above 80% of its design load.

10. Emissions Control Equipment. The utility and the commission Staff agree that the in-service testing requirements of this Paragraph are equivalent to the performance criteria stated in Paragraph 9 above. Each equipment system as set forth in Subparagraphs (a) – (d) below shall be evaluated for successful completion of in-service testing on an individual basis. The failure of the utility to achieve the emissions or removal limits specified in the in-service testing for a given system will not impact the utility's ability to include all systems demonstrated to meet the applicable emissions or removal limits in the utility's rate recovery regulatory proceeding for Plum Point Unit 1.

### a) NO<sub>X</sub> Control Equipment

- i. All major construction work is complete.
- ii. All preoperational tests have been successfully completed.
- iii. Equipment successfully meets the operational contract guarantees necessary to achieve the emission levels described in subparagraphs 10(a)(iv) and10(a)(v) below.
- iv. The equipment shall be operational and demonstrate its ability to operate at a NO<sub>X</sub> emission level of less than or equal to 0.075 lb/MMBtu over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load (665 MWnet).
- v. The equipment shall also demonstrate its ability to operate at a  $NO_X$  emission level of less than or equal to 0.080 lb/MMBtu over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load (665 MWnet).

### b) <u>SO<sub>2</sub> Control Equipment</u>

- i. All major construction work is complete.
- ii. All preoperational tests have been successfully completed.

- iii. Equipment successfully meets the operational contract guarantees necessary to achieve the emission levels described in subparagraphs 10(b)(iv) and 10(b)(v) below.
- iv. The equipment shall be operational and demonstrate its ability to operate at a SO<sub>2</sub> emission level of less than or equal to 0.11 lb/MMBtu over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load (665 MWnet).
- v. The equipment shall also demonstrate its ability to operate at a SO<sub>2</sub> emission level of less than or equal to 0.115 lb/MMBtu over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load (665 MWnet).

### c) Particulate and Opacity Control Equipment

- i. All major construction work is complete.
- ii. All preoperational tests have been successfully completed.
- iii. Equipment successfully meets the operational contract guarantees necessary to achieve the emission levels described in subparagraphs 10(c)(iv) and 10(c)(v) below.
- iv. The equipment shall be operational and demonstrate its ability to operate at a stack opacity (one hour rolling average) less than or equal to 5.4% over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load (665 MWnet).
- v. The equipment shall also demonstrate its ability to operate at a stack opacity (one hour rolling average) less than or equal to 5.7% over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load (665 MWnet).

### d) Mercury Removal Equipment

- i. All major construction work is complete.
- ii. All preoperational tests have been successfully completed.
- iii. Equipment successfully meets the operational contract guarantees necessary to achieve the emission levels described in subparagraphs 10(d)(iv) and 10(d)(v) below.

### **SCHEDULE BAM-5**

- iv. The equipment shall be operational and demonstrate its ability to operate at a mercury emission level of less than or equal to 84 X 10<sup>-6</sup> lb/MWhr(gross) over a continuous four (4) hour period while the generating unit is operating at or above 95% of its design load (665 MWnet).
- v. The equipment shall also demonstrate its ability to operate at a mercury emission level of less than or equal to 89 X 10<sup>-6</sup> lb/MWhr(gross) over a continuous 120-hour period while the generating unit is operating at or above 80% of its design load 665 MWnet).

### e) Continuous Emissions Monitoring System

i. Continuous emission monitoring systems (CEMS) are operational and demonstrate the capability of monitoring the emissions to satisfy the parameters in paragraph 9 or subparagraphs 10 (a) through (d).

\*\*Highly Confidential in its Entirety\*\*

# LARGE CAPITAL PROJECT EXPENDITURE AND BUDGET ANALYSIS

latan Unit 1, latan Common, latan Unit 2, and Plum Point

	Project Code	Parent Code	Expenditures thru Jun 30, 09 (Exci. AFUDC)	AFUDC Only thru Jun 30, 09	Project Total incl. AFUDC thru Jun 30, 09	Projected 7/2009 Thru Completion (Excl. AFUDC)	Projected 7/2009 Thru Completion (AFUDC Only)	Final Projected Project Excluding AFUDC	Final Project Including AFUDC
latan	1 Environmental	ıntal	39,370,446.31	3,225,840.79	42,596,287.10	5,876,443.69		45,246,890.00	48,472,730.79
	MI0029C	P10002	48,216.01		48,216.01	I - · · ·	£	48,216.01	48,216.01
	MI0101R	P10002	23,705.64		23,705.64	The second secon	1	23,705.64	23,705.64
	MI0123C	P10002	3,396,372.70	177,734.04	3,574,106.74		*	3,396,372.70	3,574,106.74
	MI0124C	P10002	33,204.38	4,381.53	37,585.91	1	•	33,204.38	37,585.91
	MI0137C	P10002	62,799.89	1,556.88	64,356.77		t	62,799.89	64,356.77
	MI0146C	P10002	1,141,655.76	122,264.26	1,263,920.02			1,141,655.76	1,263,920.02
	Mi0150C	P10002	1,132,065.14	140,024.01	1,272,089.15	The second party of the se	•	1,132,065.14	1,272,089.15
	MI0151C	P10002	715.63	2.00	717.63		4	715.63	717.63
	MI13038C	P10002	187,676.51	17,604.25	205,280.76	1		187,676.51	205,280.76
	MI6531C	P10002	297,333.45	6,260.31	303,593.76	ı	t	297,333.45	303,593.76
	MI93100C	P10002	48,980.00	977.04	49,957.04		1	48,980.00	49,957.04
	MI9893C	P10002	32,997,721.20	2,755,036.47	35,752,757.67	5,876,443.69	F	38,874,164.89	41,629,201.36
latan	latan Common Facilities	cilities	32,328,710.00	274,119.73	32,602,829.73	13,627,090.00	•	45,955,800.00	46,229,919.73
	MI10883C	NG0016	13,313,667.55	274,119.73	20,279,044.32	12,257,765.41	1	32,262,690.00	32,536,809.73
	MI13029C	P10002	19,015,042,45		12,323,785.41	1,369,324.59	ŗ	13,693,110.00	13,693,110.00
latan	latan 2 Construction	uo <u>i</u>	140,974,588.51	9,251,129.79	150,225,718.30	61,562,721.49	14,509,507.25	202,537,310.00	226,297,947.04
	MI10008C	NG0016	314,371.72	1	314,371.72	7,766.40		322,138.12	322,138.12
	MI10480C	NG0016	140,347,472.06	9,224,196.14	149,571,668.20	60,367,927.33	14,469,500.41	200,715,399.39	224,409,095.94
	MI10481C	NG0016	312,744.73	26,933.65	339,678.38	1,187,027.76	40,006.84	1,499,772.49	1,566,712.98
Plum	Plum Point Energy Station	y Station	79,342,791.95	9,887,570.85	89,230,362.80	8,657,208.05	6,345,416.76	88,000,000.00	104,232,987.61
	AP3930C	NG0016	261,849.26	ı	261,849.26	1,735.34		263,584.60	263,584.60
	AP3935C	NG0016	2,370,344.63	352,047.29	2,722,391.92	519,202.21	210,952.45	2,889,546.84	3,452,546.58
	AP3936C	NG0016	76,710,598.06	9,535,523.56	86,246,121.62	8,136,270.50	6,134,464.31	84,846,868.56	100,516,856.43
TOTAL	닞		292,016,536.77	22,638,661.16	314,655,197.93	89,723,463.23	20,854,924.01	381,740,000.00	425,233,585.17

Note: The amounts shown for the latan 1 Environmental and latan Common Facilities projects in the "thru Jun 30, 09" columns are amounts that have been book ed to plant in-service as of Jun 30, 2009.

Prepared by: Karen Heady, Strategic Projects

### latan Unit 2 O&M Adjustment Empire 12% Share

201	11	Bu	dget

510000 Total         510000:Steam Power Maint-Supv & Engin           511001 Total         511001:Steam Power Maint-Structure-Fa           511002 Total         511002:Steam Power Maint-Structure-Fa           512001 Total         512001:Boiler Plt Maint - Ft Unload           512002 Total         512002:Boiler Plt Maint - Stacker           512003 Total         512003:Boiler Plt Maint - Coal Pile           512004 Total         512004:Boiler Plt Maint - Coal Pile           512005 Total         512005:Boiler Plt Maint - Ash           512006 Total         512005:Boiler Plt Maint - Fuel           512007 Total         512007:Boiler Plt Maint - Air           512008 Total         512008:Boiler Plt Maint - Water           512010 Total         512010:Boiler Plt Maint - Water           512011 Total         512012:Boiler Plt Maint - Furnace           512012 Total         512012:Boiler Plt Maint - Aux Steam           512013 Total         512013:Boiler Plt Maint - Aux Steam           512015 Total         512015:Boiler Plt Maint - FT Turb/Gen           513001 Total         513002:Elec Plt Maint - FT Turb/Gen           513002 Total         513003:Elec Plt Maint - Aux Elec           513003 Total         513003:Elec Plt Maint - Transfer FF           513006 Total         513006:Elec Plt Maint - FF Comp Air           557000	**  **  **  **  **  **
510000 Total         510000:Steam Power Maint-Supv & Engin         ***           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Conveyor         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Fuel         **           512008 Total         512008:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Water         **           512011 Total         512011:Boiler Plt Maint - Furnace         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512013 Total         512015:Boiler Plt Maint - FF Turb/Gen         **           513001 Total         513002:Elec Plt Maint - Transfer FF         **           513002 Total         513003:Elec Plt Maint - Cooling         **	**  **  **  **  **
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Coal Pile         **           512005 Total         512005:Boiler Plt Maint - Ash         **           512006 Total         512006:Boiler Plt Maint - Conveyor         **           512007 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Water         **           512011 Total         512011:Boiler Plt Maint - Furnace         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512013 Total         512015:Boiler Plt Maint - AQC         **           513001 Total         513001:Elec Plt Maint - Transfer FF         **           513002 Total         513002:Elec Plt Maint - Cooling         ** <td>**  **  **  **</td>	**  **  **  **
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Air         **           512008 Total         512008:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Water         **           512011 Total         512011:Boiler Plt Maint - Furnace         **           512011 Total         512011:Boiler Plt Maint - Aux Steam         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512015 Total         512015:Boiler Plt Maint - Transfer FF         **           513001 Total         513003:Elec Plt Maint - Transfer FF         **	**  **  **  **
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Water         **           512008 Total         512008:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Cond Sys         **           512011 Total         512011:Boiler Plt Maint - Furnace         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512013 Total         512015:Boiler Plt Maint - Maint - Water         **           512015 Total         513001:Elec Plt Maint - Transfer FF         **           513001 Total         513003:Elec Plt Maint - Cooling         **	** ** **
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Coal Pile         **           512005 Total         512005:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Water         **           512008 Total         512007:Boiler Plt Maint - Water         **           512010 Total         512008:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Cond Sys         **           512011 Total         512011:Boiler Plt Maint - Aux Steam         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512013 Total         513001:Elec Plt Maint - FF Turb/Gen         **	** ** **
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Coal Pile         **           512005 Total         512005:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Water         **           512008 Total         512008:Boiler Plt Maint - Water         **           512010 Total         512008:Boiler Plt Maint - Cond Sys         **           512010 Total         512010:Boiler Plt Maint - Furnace         **           512011 Total         512011:Boiler Plt Maint - Aux Steam         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512013 Total         513001:Elec Plt Maint - FF Turb/Gen         **	** ** **
510000 Total         510000:Steam Power Maint-Supv & Engin           511001 Total         511001:Steam Power Maint-Structure-Fa           511002 Total         511002:Steam Power Maint-Struct-Fac-F           512001 Total         512001:Boiler Plt Maint - FF Unload           512002 Total         512002:Boiler Plt Maint - Stacker           512003 Total         512003:Boiler Plt Maint - Coal Pile           512004 Total         512004:Boiler Plt Maint - Ash           512005 Total         512005:Boiler Plt Maint - Conveyor           512006 Total         512006:Boiler Plt Maint - Fuel           512007 Total         512007:Boiler Plt Maint - Fuel           512008 Total         512008:Boiler Plt Maint - Water           512010 Total         512010:Boiler Plt Maint - Water           512011 Total         512011:Boiler Plt Maint - Furnace           512012 Total         512012:Boiler Plt Maint - Aux Steam           512013 Total         512013:Boiler Plt Maint - Aux Steam           512015 Total         513001:Elec Plt Maint - F Turb/Gen           513002 Total         513002:Elec Plt Maint - Transfer FF           513003 Total         513003:Elec Plt Maint - Aux Elec           514001 Total         514001:Misc Steam Plt - FF Comp Air           557000 Total         557000:Prod-Other-Other Expenses           708144 Total<	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Ash         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Air         **           512008 Total         512008:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Cond Sys         **           512011 Total         512011:Boiler Plt Maint - Aux Steam         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512015 Total         512015:Boiler Plt Maint - FF Turb/Gen         **           513001 Total         513001:Elec Plt Maint - Transfer FF         **           513003 Total         513003:Elec Plt Maint - Aux Elec         **     <	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Coal Pile         **           512005 Total         512005:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Water         **           512011 Total         512010:Boiler Plt Maint - Furnace         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512013 Total         512013:Boiler Plt Maint - Aux Cleam         **           513001 Total         513001:Elec Plt Maint - FF Turb/Gen         **           513002 Total         513003:Elec Plt Maint - Aux Elec         **	
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Air         **           512008 Total         512008:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Cond Sys         **           512011 Total         512011:Boiler Plt Maint - Furnace         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512015 Total         512015:Boiler Plt Maint - Aux Steam         **           513001 Total         513001:Elec Plt Maint - Fr Turb/Gen         **           513002 Total         513002:Elec Plt Maint - Aux Elec         **	
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Water         **           512011 Total         512011:Boiler Plt Maint - Furnace         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512013 Total         512013:Boiler Plt Maint - Aux Steam         **           513001 Total         513001:Elec Plt Maint - FF Turb/Gen         **           513002 Total         513002:Elec Plt Maint - Transfer FF         **           513003 Total         513003:Elec Plt Maint - Aux Elec         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Air         **           512010 Total         512010:Boiler Plt Maint - Water         **           512011 Total         512010:Boiler Plt Maint - Furnace         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512015 Total         512015:Boiler Plt Maint - AQC         **           513001 Total         513001:Elec Plt Maint - FF Turb/Gen         **           513002 Total         513002:Elec Plt Maint - Transfer FF         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Water         **           512011 Total         512010:Boiler Plt Maint - Furnace         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512015 Total         512015:Boiler Plt Maint - Unclassifid E         **           513001 Total         513001:Elec Plt Maint - FF Turb/Gen         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Water         **           512011 Total         512011:Boiler Plt Maint - Furnace         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512013 Total         512013:Boiler Plt Maint - Unclassifid E         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Air         **           512010 Total         512010:Boiler Plt Maint - Water         **           512011 Total         512011:Boiler Plt Maint - Furnace         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **           512013 Total         512013:Boiler Plt Maint - AQC         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Cond Sys         **           512011 Total         512011:Boiler Plt Maint - Furnace         **           512012 Total         512012:Boiler Plt Maint - Aux Steam         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **           512007 Total         512007:Boiler Plt Maint - Air         **           512010 Total         512010:Boiler Plt Maint - Cond Sys         **           512011 Total         512011:Boiler Plt Maint - Furnace         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512007 Total         512007:Boiler Plt Maint - Fuel         **           512008 Total         512008:Boiler Plt Maint - Water         **           512010 Total         512010:Boiler Plt Maint - Cond Sys         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512007 Total         512007:Boiler Plt Maint - Fuel         **           512008 Total         512008:Boiler Plt Maint - Water         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512007 Total         512007:Boiler Plt Maint - Air         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **           512006 Total         512006:Boiler Plt Maint - Fuel         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **           512005 Total         512005:Boiler Plt Maint - Conveyor         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **           512004 Total         512004:Boiler Plt Maint - Ash         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **           512003 Total         512003:Boiler Plt Maint - Coal Pile         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **           512002 Total         512002:Boiler Plt Maint - Stacker         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **           512001 Total         512001:Boiler Plt Maint - FF Unload         **	**
510000 Total         510000:Steam Power Maint-Supv & Engin         **           511001 Total         511001:Steam Power Maint-Structure-Fa         **           511002 Total         511002:Steam Power Maint-Struct-Fac-F         **	**
510000 Total 510000:Steam Power Maint-Supv & Engin ** 511001 Total 511001:Steam Power Maint-Structure-Fa **	**
510000 Total 510000:Steam Power Maint-Supv & Engin **	**
	**
509000 Total 509000:Prod Elec Oper-Allowances **	**
506000 Total 506000:Misc Steam Power Operations **	**
505010 Total 505010:Prod Elec Oper-Turb/Gen **	**
505007 Total 505007:Prod Elec Oper-Facilities **	**
502015 Total 502015:Steam Oper-Water Pollution Con **	**
502014 Total 502014:Steam Oper-Air Pollution Contr **	**
502013 Total	
502012 Total	**
502010 Total 502010:Steam Oper-Solid By-Products **	**
502004 Total 502004:Steam Oper-Water **	**
502002 Total 502002:Steam Oper-Fuel **	**
502001 Total 502001:Steam Oper-Boiler **	**
501511 Total 501511:Fuel Hndlg-fuel additives **	**
501510 Total 501510:Fuel Handling - Conveyor **	**
501509 Total 501509:Fuel Handling - Coal Pile **	**
501508 Total 501508:Fuel Handling - Stacker **	**
501506 Total 501506:Fuel Hndlg-Receive Coal **	**
501500 Total 501500:Fuel Handling Costs **	**
501400 Total 501400:Fuel Exp-Residuals **	**
500000 Total 500000:Prod-Steam Oper-Supv & Enginr **	

<sup>\*\*</sup>Took out Capital dollars, fuel and fuel additives to derive annual OM adjustment Data from 2010-2014 JO - EDE 091023.xls received from Roger Nickell

SCHEDULE BAM-8

### latan Unit 1 AQCS Adjustment Empire 12% Share

2011 Budget

Total Adjustment		350	0,007
501302 Total	501302:Fuel Exp-Additives-PAC	**	**
501301 Total	501301:Fuel Exp-Additives-Ammonia	**	**
501300 Total	501300:Fuel Exp-Additives - Limestone	**	**

Data from 2010-2014 JO - EDE 091023.xls received from Roger Nickell

### Iatan Common Properaty O&M Adjustment Empire 12% Share

2011 Budget

Total Adjustment			(216,136)
926511 Total	926511:PR Tax, Pens & Bnfits on O&M	**	**
708144 Total	708144:Payroll Taxes- Billed	**	**
557000 Total	557000:Prod-Other-Other Expenses	**	**
501509 Total	501509:Fuel Handling - Coal Pile	**	**
163200 Total	163200:Stores Exp Undis-Production	**	**

Data from 2010-2014 JO - EDE 091023.xls received from Roger Nickell

AQCS Consumables by Generating Unit

					Plum				
	ı	latan Unit 1	remember of the second	latan Unit 2	Point Unit		Asbury	SLCC	Total
Ammonia	*		* * *	1-	** **	*	**	*	988,948
Limestone	*		* *	<b>b</b>	* *	<b>*</b>	**	*	450,626
PAC	*		* *	<b>3</b> .	**	* * *	* *	*	725,609
Total		350,008		612,371	471,166		503,054	228,584	2,165,183

### **AFFIDAVIT OF BLAKE A. MERTENS**

STATE OF MISSOURI	)	
	)	SS
<b>COUNTY OF JASPER</b>	)	

On the 29<sup>th</sup> day of October, 2009, before me appeared Blake A. Mertens, to me personally known, who, being by me first duly sworn, states that he is the Associate Director of Strategic Projects of The Empire District Electric Company and acknowledges that he has read the above and foregoing document and believes that the statements therein are true and correct to the best of his information, knowledge and belief.

Blake A. Mertens

Subscribed and sworn to before me this 29<sup>th</sup> day of October, 2009.

Ville L. Krame.

My commission expires: (0-30.10)

VICKI L. KRAMER-GIBSON Notary Public - Notary Seal STATE OF MISSOURI Jasper County - Comm#06482169 My Commission Expires Oct. 30, 2010